	Items of work	Unit	Quantity
	(*c*) G. I. ridge sheeting plain, 24 B. W. G. 2 feet wide with washers bolts, etc..	R.ft.	90
	(*d*) Teakwood work with woodoiling two coats	C.ft.	45·92
	(*e*) Teakwood door panelled, 1½" shutters with bolts, hinges, etc., frames 4½"×6". *Vide* Drg. No. M. 149.	S.ft.	130
	(*f*) Teakwood glazed windows 1¼" shutters with bolts, hinges, etc., frames 4"×5" with iron bars ¾" dia., 4" C to C. *Vide* Drg. No. M. 149.	,,	155
	(*g*) Silver grey silicate painting three coats..	Sqr.	9·51
5.	(*a*) Rolled steel I beams including fixing charges	Cwt.	3·21
	(*b*) Steel rails S. M. R. Secondhand 40 lbs. including cutting to sizes and fixing.	,,	73
	(*c*) One and a half inches Angle Iron brackets with anchoring bolts, etc., to support the roof.	Each	23
6.	Cement concrete (1 : 2½ : 5) foundation	C.ft.	89
7.	Constructing drains 9" deep all round the Oil and Pump House with surki concrete and cement plastering ½" thick.	R.ft.	130

N.B.—For items 4 (a) and (b) zinc sheets will be supplied by the Department. Price to be quoted for issuin screws and washers and fixing the sheets.

B. KRISHNA RAO,
For *Chief Electrical Engineer*
to the Government of Mysore

KOLAR DIVISION.

FORM OF ADVERTISEMENT.

Dated 22nd August 1927.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kolar Division, up to 2 P.M., on 12th September 1927, for restoring Kiruvara Minor Tank, Reg. No. 88, Srinivaspur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1928.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar, between the hours of 11 A.M. and 2 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified willibe executed :—

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of rupees two hundred only in Cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Kiruvara Minor Tank," Srinivaspur Taluk, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond : in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The rates in the tender should be noted in figures as well as in words.

Items	Per	Quantity	Rate	Cost
I. Bund—				
1. Earthwork including watering and tamping	C.yd.	5,470		
2. Turfing	S.yd.	4,359		
3. Cutting grips	No. of grade	30		
4. Jungle clearing (Prickly pear thick), cutting hongey trees and removing roots ...	,,	25		
5. New stone work	C.yd.	1,017		
6. Old stone work	,,	81		
7. Providing new grade stones with index stones with painting	No.	30		
8. Providing new B. M. stones	,,	2		
9. Do Registered No. stone and date stone with painting	,,	2		
II. Sluices 1 and 2—				
1. Cutting bund, examining and repairing the existing sluices with necessary masonry works	Each	2		
III. Waste Weir, left—				
1. Earthwork excavation	C.yd.	72		
2. Burnt brick in surki mortar	C.ft.	506		
3. Burnt stone slabs 6" thick	S.ft.	307		
4. Plastering with surki mortar	Sqr.	6·23		
5. Rough stone work new	C.yd.	43		
Total ...	...	...	...	...
Contingencies ...	...	...	...	...
Grand Total, Rupees ...	...	...	...	...

S. SRINIVASA IYER,
Executive Engineer.

OFFICE OF THE EXECUTIVE ENGINEER, SPECIAL DIVISION.

Notification dated 22nd August 1927.

"It is hereby notified for the information of the public that the Second Class Travellers Bungalow at Mysore will be closed to the public. The building ceases to be a Travellers Bungalow."

V. V. KARVE,
Executive Engineer.

MYSORE DISTRICT.

Notice No. 59, dated 20th August 1927.

Tenders are hereby invited for the supply of one waggon of charcoal and four waggons of fuel for the tunnel work at Hulikere, Mandya Taluk F. O. R. Byaderahally Railway Station within 15 days from the date of accepting the tender. Each tender should accompany with a deposit of Rs. 50 as earnest money.

If the same is not delivered within the prescribed time by the accepted tenderer, the deposit money will have to be forfeited.

B. KRISHNASWAMI IYENGAR,
Executive Engineer,
No. III Tunnel Division.